

Mill River Mechanical Co. LLC

112 Pleasant Street, Easthampton, MA 01027
Phone 413-555-0100 | millrivermech@gmail.com

Quote No. Q-2026-114

Job No. J-2601

Date: September 11, 2026

QUOTATION

Oil Boiler to Air-Source Heat Pump Conversion

Prepared for

Ellen Pomeroy
71 Park Street
Easthampton, MA 01027

Job site

71 Park Street, Easthampton, MA 01027
Single-family residence, approx. 2,100 sq ft
Original construction circa 1920s

Thank you for having us out to look at the house. This quote covers the complete removal of the existing oil-fired boiler and above-ground oil tank and the installation of a ducted air-source heat pump system sized to carry the whole house, together with the electrical and ductwork work required to support it. Equipment has been selected against a Manual J load calculation performed for the house on September 9, 2026.

Scope of Work and Pricing

No.	Description	Price
1	Heat pump system. Three (3) ducted air handlers with matched outdoor units, sized by Manual J load calculation. Includes line sets, condensate management, outdoor equipment pads, low-voltage control wiring and thermostats.	\$19,400
2	Electrical service upgrade. Upgrade of the existing service to 200A, new panel and grounding, and dedicated circuits and disconnects for each outdoor unit and air handler.	\$5,800
3	Ductwork modification and sealing. Modification of existing distribution to suit the new equipment, new trunk and branch runs where required, sealing of accessible joints, and register and grille adjustment for balance.	\$4,200
4	Oil system removal. Decommissioning, removal and disposal of the existing oil boiler and oil storage tank, capping of the associated piping and flue, and site cleanup.	\$2,300
5	Permits, startup and commissioning. Mechanical, electrical and plumbing permits, inspections, refrigerant charge verification, airflow balancing, control setup, and homeowner walkthrough of system operation.	\$2,800
Total		\$34,500

Pricing includes all labor, materials and equipment described above. Massachusetts sales tax on materials is included. Pricing does not include electrical utility service charges levied by the utility, asbestos or hazardous material abatement if encountered, structural or carpentry repair, plaster or drywall patching beyond what is needed for access, or painting.

Terms

Term	Detail
Quote validity	30 days from the date of this quote
Deposit	40% of the total (\$13,800) on contract signing
Balance	Due on completion and homeowner walkthrough
Estimated duration	5 to 7 working days

Work will be scheduled once the signed contract and deposit are received. Heat pump equipment lead time is currently running two to three weeks; we will confirm the install dates with you when the equipment ship date is set. The oil tank removal will be coordinated so the house is not without heat for more than one working day.

Workmanship and Warranty

Mill River Mechanical warrants its workmanship for one (1) year from the completion date. Equipment carries the manufacturer's warranty, which we will register on your behalf at commissioning. All work will be performed by our own licensed technicians under permit and inspected by the City of Easthampton.

Questions we have not answered yet

You asked about rebates that may be available for this work. We have not researched that question yet and this quote makes no assumption about it. Mill River Mechanical will confirm current program eligibility and put the answer in writing before the contract is signed. The pricing above is the full contract price and is not reduced by any rebate.

Questions on this quote can go to Dana Mercier or Gene Kowalczyk at 413-555-0100, or by email to millrivermech@gmail.com.

Acceptance

Signing below accepts this quote and authorizes Mill River Mechanical Co. LLC to order equipment and schedule the work described above.

CUSTOMER — ELLEN POMEROY

 Signature
 Ellen Pomeroy
 Homeowner
 Date: _____

MILL RIVER MECHANICAL CO. LLC

 Signature
 Dana Mercier
 Member
 Date: _____